

EAST MISSISSIPPI COMMUNITY COLLEGE
STUDENT UNION BUILDING
DELIVERY ACCESS ROAD PAVING PROJECT

SPECIFICATIONS

Scope of Work

The project will consist of paving approximately 20,000 sq. ft. of existing roadway with an average of 5 inches of Hot Mix asphalt, graded to tie into and accommodate the existing curbs and concrete pavements. The contractor shall provide the necessary equipment, materials, and labor to complete the project.

Prior to the submission of bids, all contractors shall inspect the site and location for the project, take field measurements, and request additional information on conditions and limitations of the project. Any information requested will be provided in written form and disseminated to all prospective bidders.

General Specifications

1. The contractor shall remove approximately 3 inches of existing material to get on grade and prepare base as required. The contractor shall stockpile excess material that is removed from roadway on the property as designated by owner.
2. The contractor shall install a base course of 3 inches average compacted depth of asphalt binder to grade.
3. The contractor shall install a tack coat to bond the bottom course of asphalt with the top course, which shall consist of 2 inches average compacted asphalt as the surface.
4. Final grade of paved surface shall have +/- 2% slope away from existing curb, as necessary.
5. The contractor shall cleanup the site upon completion of the project.

Associated Documents and Site Information

1. Instructions for Bidders (See Attached)
2. Sheet S-1 – Location of Project Site and Limits (See Attached)